


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.  
H. Buehler No. 6.

SEC. 33 T. 17 R. 8W  
NEc NE  
440' S 440' W of NE Cor.

Total Depth. 3216' (CFL 3215')  
Comm. 2-4-41 Comp. 2-22-41  
Shot or Treated.  
Contractor.  
Issued. 5-31-41

County. Ellsworth



CASING:  
10 $\frac{3}{4}$ " 213' Cem.  
6 " 3159' Cem.

Elevation.

Production. Echo. Pot. 10,421 B  
Allowed Pot. 3000B  
No wtr

Figures Indicate Bottom of Formations.

shale	40
shale & shells	217
shale & shells	840
shale & salt	1050
shale & shells	1130
shale & lime	1300
lime brkn	1515
shale & shells	1695
shale & lime	1855
shale & shells	2320
shale & shells	2400
lime	2545
lime	2715
lime brkn	2775
lime	2920
break - sft	2933
lime	2980
shale	2990
lime	3150
shale	3161
dolomite	3165
lime	3195
lime	3216
Total Depth.	

Total depth from cement  
floor level 3215

Top of Arbuckle lime 3158

Total fillup w/oil 3150  
2-22-41 swabbed 226 BO in 4 H.  
2-25-41 this well was given an  
Echo. Pot. 10,421 BO, estab.  
a maximum allowed pot. of 3000  
BO, no wtr.

Note: All of the above footages  
are calculated from cement  
floor level.