


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

CONTINENTAL OIL CO.
J.F. Rolfs No. 7.

SEC. 34 T. 17 R. 8W
NE NE NW NW
2200' N SL 1300' E WL

County. Ellsworth

Total Depth. 3254'
Comm. 3-19-38 Comp. 4-7-38
Shot or Treated. 1000 Gals.
Contractor. Fain Drlg. Co.
Issued. 5-14-38 Rotary 3241
Cable 3254



CASING:
10 $\frac{3}{4}$ " 211'
7 " 3239'

Elevation.

Production. Pot. 1925.94 B.
No wtr.

Figures Indicate Bottom of Formations.

surface sand	211
blue shale & shells	300
red rock & shells	465
shale, gyp & shells	795
salt	896
shale & lime shells	1516
lime & shale	1616
brkn lime	1852
shale & lime shells	2093
shale	2170
brkn lime	2355
shale & shells	2420
lime	3195
shale	3241
Arbuckle lime	3254
Total Depth.	

Plug was drilled and well filled
up 2500' with oil in 1 $\frac{1}{2}$ hrs.

No pumping test on well before acid.

4-12-38 well acidized with 1000 gals.
acid.

On initial potential test well pump-
ed 320.99 bbls oil 1st 4 hrs and
361.33 bbls oil last four hrs giving
Pot. 1925.94 bbls oil 24 hrs - No
wtr.

Daily allowable based on 3.52% is
67.79 Bbls.

Arbuckle lime 3239-3254