


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
J.F. Rolfs No. 10

SEC. 34 T. 17 R. 8W.
NWc NW
440' E 440' S of NW cor.

Total Depth. 3224
Comm. 3-14-41 Comp. 4-1-41
Shot or Treated. 2000 gal acid.
Contractor. Parker Drilling Co.
Issued. 6-28-41

County Ellsworth.



CASING.

95/8" 199'
6" 3186'

Elevation.

Production. Pot. 34,126 B.

Figures Indicate Bottom of Formations.

surface & soil	60
shale and shells	205
shale, shells, red bed	409
shale and shells	855
salt and shells	1050
shale and lime	1160
lime	1200
shale and lime	1268
shale and shells	1445
lime broken	1670
shale and shells	1702
broken lime and shale	1795
lime broken	1935
shale and shells	2080
shale and lime strks	2245
shale	2320
lime broken	2415
lime	2630
shale and limo	2655
limo	2718
shale and shells	2817
lime broken	2857
lime	2964
limo & shale strks	3019
limo	3133
broken lime & shale	3185
shale	3194
limo	3224
Total Depth.	

Top of Arbuckle 3185