


CONTINENTAL OIL CO.
H.F. Janssen No. 11B.

SEC. 34 T. 17 R. 8W
NW NE SW
330' S 990' W of NEcSW $\frac{1}{4}$

Total Depth. 3236'
Comm. 7-15-37 Comp. 8-7-37
Shot or Treated. 4000 Gals.
Contractor. Parker Drlg. Co.
Issued. 12-4-37

County. Barton



CASING:
10 $\frac{3}{4}$ " 181'4"
7" 3205'6"

Elevation.

Production. Pot. 740 Bbls.

Figures Indicate Bottom of Formations.

cellar	8-98-9
clay & sandstone	40
shells	70
red bed & shells	185
clay & shells	217
shale & shells	345
shale	390
anhydrite	399
shale & shells	740
shale	887
salt	935
salt & shale	1080
brkn lime shale	1190
shale & shells	1460
sand	1476
brkn lime	1480
brkn lime & shale	1550
shale & lime	1620
brkn lime	1634
shale & lime shells	1720
brkn lime	1824
shale & lime shells	1856
shale & shells	1980
lime & shale	2142
paratise of iron	2144
shale & lime	2147
shale & lime shells	2217
shale & shells	2325
shale & lime shells	2383
shale	2419
brkn lime & shale	2465
lime	2747
brkn lime	2870
lime	2917
lime & shale	2945
shale & shells	2963
lime	3203
shale & lime	3205
Siliceous lime	3213
sdv lime	3236
Total Depth.	

Well was given 740 bbls of oil
on 24 hr potential test.
Pumped 141.83 oil 1st 4 hrs and
123.36 last 4 hrs. No wtr.

Top of Siliceous lime 3204