

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
H.F. Janssen No. 12-B.

SEC. 34 T. 17 R. 8W.
NWc SW
440' South 440' East W $\frac{1}{2}$ Cor.

Total Depth. 3247
Comm. 6-23-40 Comp. 7-17-40
Shot or treated.
Contractor.
Issued. 10-5-40

County Ellsworth.



CASING.

103/4" 193'
7" 3243'

Elevation.

Production: Pot. 567.09B,
45 BW.

Figures Indicate Bottom of Formations.

shale and shells	690
shale	860
salt	1060
shale and shells	1415
sdv lime	1440
broken lime	1445
shale	1480
lime	1535
shale and lime	1680
shale and shells	1915
shale and shells	2315
broken lime	2440
limo	2660
broken lime	2700
limo	2720
shale and shells	2820
lime	3205
conglomerate	3241
shale	3244
dolomite	3247
Total Depth.	

Total Depth from cement floor level 3246

Top of Arbuckle lime from cement floor level 3241.

7-12-40 acidized with 500 gal acid.
7-13-40 acidized with 1000 gal acid
hole filled up 1100' with oil.
7-18-40 Acidized with 2000 gal acid.

7-20-40. On potential test the well pumped 189.03 bbls oil and 15BW
in 8 hours, giving the well a 24 hour pot. of 567.09 bbls oil and 45 BW