


CONTINENTAL OIL CO.
J.F. Rolfs No. 1

SEC. 34 T. 17 R. 8W
SWc NE

Total Depth. 3256
Comm. 12-28-36 Comp. 1-25-37
Shot or Treated. 4000 Gals. Acid.
Contractor. E.J. Shaffer
Issued. 4-17-37

County Ellsworth.



CASING.

13" 205'
7" 3244'

Elevation.

Production. Pot. 1107B.

Figures Indicate Bottom of Formations.

CELLAR	8
sand and sholls	38
shale hard sholls	104
shale hard sholls	206
shale and sholls	785
shale & sholls & salt	1045
shale & sholls	1100
broken limo	1163
shale and sholls	1285
shale & lime sholls	1408
shale and sholls	1538
shale and lime	1628
broken lime & shale	1725
shale and sholls	1906
shale and sholls	2 340
lime and shale	2443
shale and lime	2518
lime	2828
lime and shale	2904
lime	2952
broken limo	3005
lime and shale	3050
broken limo	3134
lime	3186
lime and shale	3207
sdv shale rod	3211
broken limo	3219
sand	3226
shale	3243
lime	3256

Total Depth.

1st show oil and gas 3245

increase of oil and gas 3246

Siliceous Lime 3251