


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
506 East Murdock, Wichita, Kansas

Company. CONTINENTAL OIL COMPANY
Farm- Hodgson No. 1

SEC. 5 T. 17 R. 8W
NE NE NE

Total Depth. 3303
Com.m. 1-29-53 Comp. 2-10-53
Shot or Treated
Contractor. Garvey Drlg. Co.
Issued. 4-4-53

County Ellsworth
KANSAS



CASING:
10 3/4" 307' cem. w/250 sx
5 1/2" 3286' cem. w/150 sx

Elevation. 1597 RB

Production. Phy. Pmp. Pot.
79 BO 1 BW 24 hrs.

Figures indicate Bottom of Formation.

surface soil & sand	70
sand & shells	145
shale & shells	1035
shale & sandy lime	1125
lime & shale	1540
shale & shells	1745
lime & shale	2460
lime	2624
shale & lime	2741
lime	2755
lime & shale	2801
lime	3130
shale & lime	3205
lime	3235
shale & sand	3285
lime	3303 RTD
Total Depth	

Tops: Sch.	
Heebner	2623
Brown Lime	2745
Lansing	2779
Base-K. C.	3119
Viola	3178
Simpson	3230
Arbuckle	3281

DST: #1, 3286-93' open
1 hr. rec. 21' slightly oil
cut mud, 690# BHP FOP
DST: #2 3290-3303' open
1 hr. rec. 40' oil cut mud,
690# BHP.

Producing from arbuckle open
hole 3286-3303.