

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 503 East Murdock, Wichita, Kansas


COPY

Company- ROCKET DRILLING COMPANY  
 Farm- Andrews No. 1

SEC. 4 T. 17 R. 8W  
 C 3/2 SE SW

Total Depth. 3206  
 Comm. 8-25-54 Date. 9-8-54  
 Shot or Treated.  
 Contract. Rocket Drilling Co., Inc.  
 Issued. 12-4-54

County Ellsworth  
 KANSAS



CASING:

8 5/8" OD 231' cem. w/150 sx  
 5 1/2" OD 3201' cem. w/100 sx

Elevation. 1680 R.B.

Production. 232 BOPD, no wtr.

Figures Indicate Bottom of Formations

shale red & shells 130  
 blue shale & shells 231  
 shale & shells 275  
 iron & shale 290  
 shale 530  
 shale & shells 834  
 salt 980  
 lime & shale 1110  
 lime 1365  
 sand 1370  
 lime 1490  
 lime & shale 1640  
 sand 1650  
 shale 1675  
 shale & lime 1900  
 shale 2145  
 lime & shale 2360  
 lime 2455  
 lime & shale 2767  
 lime 3060  
 lime & shale 3129  
 lime 3152  
 Simpson 3189  
 shale & sand 3200  
 Arbuckle 3202 RTD  
 Arbuckle 3206  
 Total depth

Drill Stem Tests:

DST #1: 3155-99, open 1 hr, recovered  
 10 ft. mud; BHP 830#.

Scout Tops:  
 Lansing 2742  
 Simpson 3151  
 Arbuckle 3200

GEOLOGICAL TOPS:

Heebner 2603  
 Brown lime 2724  
 Lans.-KC 2742  
 Shaly Conglomerate 3105  
 Simpson 3151  
 Simpson sand 3164-72  
 Simpson sand 3195-3200  
 Arbuckle 3200  
 RTD 3202  
 5 1/2" 3201  
 Cable TD 3206

Remarks:

No electric log made.  
 Cable Tools: Drilled plug and drilled  
 deeper to 3206; tested approximately  
 1 BOPH; 500 gals. acid down casing;  
 swab load back and swabbed 17 bbls.  
 oil, no wtr. in 7 hrs; swab 17 bbls.  
 oil, no wtr. in 6 hrs; swab 2 1/2 to 3  
 BOPH, no wtr. POP; State Phy. Pot.  
 232 BOPD, no wtr.