

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


COPY

Company-ROCKETT DRILLING CO., INC.
Farm-Andrews No. 2

SEC. 4 T. 17 R. 8W
S/2 S/2 SW

Total Depth. 3210
Comm. 1-7-55 Comp. 2-9-55
Shot or Treated.
Contractor. Rockett Drilling Co., Inc.
Issued. 8-6-55

County Ellsworth
KANSAS



8 5/8 217' w/ 150 sx cmt.
5 1/2 3208' w/ 100 sx cmt.

Elevation. 1678 RB

Production. IP 438 BOPD from
Arbuckle

Figures indicate Bottom of Formations

post rock	30
shale	110
sand & shale	195
shale & shells	1070
lime & shale	1335
lime	1365
sand	1385
lime	1480
sand	1485
lime	1760
lime & shale	2035
shale	2250
lime & shale	2415
lime	2510
lime & salt	2622
lime	2845
K. C. lime	2953
lime	3027
lime & shale	3094
lime & conglomerate	3170
Simpson	3207
Arbuckle	3210
Total Depth	

TOPS:	
Heebner	2594
Brown lime	2712
Lansing	2730
Shaley conglomerate	3099
Simpson sandy lime	3145
Simpson sand	3165
sand	3170
sand	3181
sand	3200
Arbuckle	3207

DST #1: 2746-2845, open 1 1/2 hrs., rec.
1560' gas above fluid, 690' VSO&GCMW,
Fp 120-320#, BHP 980#

DST #2: 3151-97, open 1 hr., rec. 30'
mud w/ small amt. of OCM in tool.
BHP 900#

No electric log made

DP, DD 3210. 1/2 BOPH, nat. NW, ran
tbg. & acid w/ 500 gal. thru tbg.
1200# press: broke to 600# pmp.
11 BOPH, NW, Fluid level 2900'