

COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdoch, Wichita, Kansas

Company- THE ELDORADO REFINING COMPANY
Farm- Andrews No. 2

SEC. 4 T. 17 R. 6W
NW NW NW

Total Depth. 3308
Comm. 8-16-52 Comp. 8-27-52
Shot or Treated.
Contractor. Scourling Drilg. Co.
Issued. 10-10-52

County Ellsworth
KANSAS



Elevation. 1690 FT

Production. 132 BOPD & NW

Figures Indicate Bottom of Formations.

sand, clay, red bed & shale	345
shale	380
anhydrite	395
shale & red bed	600
shale	900
salt & shale	1030
lime & shale	2040
shale	2260
shale & lime	2415
lime	2580
lime & sandy shale	2705
lime	3078
lime & congl.	3130
shale & congl.	3195
lime	3240
sandy lime	3280
lime	3290
shale	3304
arbuckle lime	3308
Total Depth	

Tops: D.F.	
Heebner	2613
Toronto	2635
Brown Lime	2740
Lansing	2765
Base-K. C.	3075
Congl.	3105
Viola	3190
Sand	3233
Arbuckle	3301

DST: 3055-75' open 30
min. rec. 15' mud, 3' of
it oil cut BHP Off.
DST: 3302-05' open 1 hr.
rec. 170' clean oil &
50' wtr BHP 900#.

D.P. C.C.O. to R.T.D. 3305 D.F.,
900' OIH/14 hrs. \$ 2 BOPH/4 hrs.
\$ 2 BOPH avge/8 hrs. F.U. 2420'
OIH/36 hrs.