


AUTO-ORDNANCE CORP.
Frank Johnson No. 1

SEC. 8 T. 17 R. 3 W.
CW $\frac{1}{2}$ SW NE

DISCOVERY WELL

Total Depth. 3460
Comm. 6-25-42 Comp. 8-2-42
Shot or Treated.
Contractor. Ingling and Parker.
Issued. 8-15-42

County McPherson.



CASING.

103/4" 345'
65/8" 3447'

Elevation. 1334 *KIT*
Production Pot. 2247 B.

Figures Indicate Bottom of Formations.

shale and shells	338	shalo	2745
anhydrite lime	350	lime hard	2760
shells and shalo	360	lime and shalo	2825
lime	405	lime sholl and shalo	2875
shale and shells	480	shalo	2899
red bed and shells	490	chat	2924
lime and shale	770	chat and limo	2955
shale	785	chat	3085
lime	820	chat and shalo	3095
lime and shalo	845	shalo	3110
lime	935	limo and shalo	3150
lime and shalo	1103	shalo and shells	3260
shale	1165	shalo	3311
shale and shells	1375	limo	3322
lime and shale	1475	chat and shale	3330
lime	1515	shalo	3334
limo and shalo	1560	sand	3336
shale and shells	1600	limo and shalo	3343
lime and shalo	1780	chat and shalo	3355
limo	1817	shalo and limo	3390
shale and limo	1830	limo	3445
sand limo and shale	1842	coring	3460
shale and shells	1855		
lime and shale	1910	Total Depth.	
lime	1925		
lime and shalo	2090	Tops.	
shale and shells	2160	Simpson shalo	3433
shale and limo	2290	Simpson dolomite	3444
lime	2322	Simpson sand	3451
sdv lime	2339	sand	3460
broken limo and shalo	2353		
broken sdv limo	2390		
broken limo	2430		
limo	2461		
broken sand and shalo	2480		
shalo	2498		
lime hard	2517		
broken limo and shale	2520		
lime	2568		
broken limo and shalo	2610		
limo and shalo	2650		
lime	2680		
	3470		

Production - 2247 B. per day
in Simpson

COPY

3451
1334
-2117 RT etc