

Plotted gwr

CITIES SERVICE OIL CO. ET AL
Wessler No. 2.

SEC. 19 T. 17 R. 9W
CWL E $\frac{1}{2}$ E $\frac{1}{2}$ SE
1320' N 440' W SE Cor.


Total Depth. 3228'

Comm. 1-29-40 Comp. 2-16-40
Shot or Treated, 2000 Gals. 2-19-40

Contractor. R.W. Rine Drlg. Co.

Issued. 3-23-40 Rotary 3221 SLM
Cable 3221-28

County. Ellsworth



CASING:
8 5/8" 212'
5 3/16" 3221'

Elevation.

Production. Pot. 2163 B. Echo.
No wtr

Figures Indicate Bottom of Formations.

surface	76
shale & shells	212
gyp, shale, red bed	550
shale & shells	780
anhydrite shells	811
anhydrite	835
salt, shale, shells	1100
shale & shells	1266
shale	1390
shale & shells	1624
shale	1695
shale & shells	1792
shale & lime	1871
shale	2345
shale & lime	2437
lime brkn	2500
shale & lime	2642
lime	2843
lime brkn	2931
shale & lime	3029
lime	3223
T.D. rotary 3223=3221 SLM	
lime	3228
Total Depth.	

Corr. Top Arbuckle 3220
Penetration 8

Fillup: 450' oil 1 $\frac{3}{4}$ hrs
1000' oil 2 $\frac{3}{4}$ hrs
2800' oil 4 $\frac{1}{4}$ hrs
3000' oil 5 $\frac{1}{4}$ hrs