

Plotted
E.M.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO. ET AL
Wesseler No. 3.

SEC.19 T.17 R. 9W
CNL NW SE
330'S 660'E Center

Total Depth. 3236'
Comm. 10-27-40 Comp. 11-16-40
Shot or Treated.
Contractor. R.W.Rine Drlg.Co.
Issued. 12-21-40

County. Ellsworth



CASING:
8 5/8" 207' Cem.
5 1/2" 3216' Cem.

Elevation.

Production. Echo.Pot.7204 B.
No wtr

Figures Indicate Bottom of Formations.

shale & shells	925
salt, shells, shale	1255
anhydrite	1310
shale & shells	1360
shale & lime	1485
shale & shells	1650
lime brkn	1740
shale & shells	2490
shale & lime	2595
lime	2790
shale	2870
lime	2981
lime sft	3013
lime	3195
shale & lime	3212
lime Arbuckle	3213
3213 Rot.T.D. =3218 SLM	
lime	3236
Total Depth.	

Corr. Top Arbuckle 3217
Penetration 19

500 Gals. & 2000 Gals. 11-13-40
2500 Gals. 11-17-40

Fillup: 525' oil in 1 hr at 3220
1600' oil in 3 1/2 hrs at 3223
2250' oil in 7 1/2 hrs at 3226
2350' oil in 8 hrs at 3226