


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg. Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY  
Farm - Wesseler No. 9

SEC. 19 T. 17 R. 9W  
SE SE SE  
330' N, 330' W of SEC.

Total Depth. 3216'  
Comm. 10-2-48 Comp. 10-18-48  
Shot or Treated. None  
Contractor. Corbett-Barbour Drlg. Co.  
Issued. 12-18-48

County. Ellsworth  
KANSAS



Elevation. 1767.9 feet.

Production. Pmpd. 63 oil, 16 wtr.  
24 hrs.

CASING:

8 5/8" 327' cem w/175 sx., & 200# C.C.  
5 1/2" 3214' cem w/150 sx.

Figures Indicate Bottom of Formations.

shale, shells 330  
redbed, shale, shells 460  
shale, shells 915  
salt 1140  
shale, shells 1420  
shale, lime 2025  
shale 2310  
shale, lime 2480  
shale 2585  
lime 2815  
lime, shale 2840  
Corr. 2840 = 2850 SLM  
shale, lime 2885  
lime 3213  
3213 RTD = 3214 SLM  
lime 3216  
total depth

Tops: Corr:

Lansing 2890  
Simpson 3202  
Arbuckle 3213

Penetration 3'

Fillup:

325' oil in 2 3/4 hrs.  
425' oil in 3 1/4 hrs.  
760' oil in 4 1/2 hrs.  
1200' oil in 6 1/2 hrs.  
1435' oil and show water in 7 1/2 hrs.  
2200' oil in 21 1/2 hrs.

Hole making 22 gals wtr pr hr..