

Plotted

SLICK-PRYOR AND LOCKHART.
Wilkins No. 1-BSEC. 18 T. 17 R. 9W
SWc SWTotal Depth. 3285
Comm. 5-29-34 Comp. 8-1-34
Shot or Treated
Contractor.
Issued. 9-1-34

County. Ellsworth.

CASING.

20"	139'	10"	1895'
15"	360'	8"	2555'
133/8"	527'	6"	3061'
		5"	3256 UR 3263'

Elevation.

Production. Potential
1070 g. 48 hours.

Figures Indicate Bottom of Formations.

cellar	12	lime	2125
yellow sand mud	130	red rock	2130
water sand	140	lime	2155
shale blue	145	1 BWPHR 2180-2190	
red rock	205	shale blue	2240
sdv shale	220	lime	2265
red rock	235	shale blue	2300
shale blue	385	lime	2330
red rock	522	shale	2350
anhydrite lime	545	hole caving.	
red rock	760	lime	2370
shale white	805	shale	2380
red rock	850	lime hard	2395
shale light	965	broken lime	2400
shale dark	975	shale blue	2450
salt	1260	lime	2470
shale	1265	shale	2490
lime	1285	lime	2520
shale	1290	shale	2525
lime	1295	show of gas 2525	
shale	1310	water sand	2545
hole caving dumping water		HFV 2525-2545	
lime	1320	lime 1 BWPHR 2665-2675	2660
shale	1330	shale	2665
lime	1340	lime	2785
shale	1370	shale blue	2800
lime	1415	lime	2850
shale	1430	red rock	2860
lime	1460	shale grey	2910
shale	1480	lime hard	3044
red rock	1495	sdv lime soft	3057
lime	1555	lime hard	3226
shale	1570	shale blk	3231
lime	1605	lime	3242
4 BWPHR 1610-1625		conglomerate	3254
sdv lime	1620	lime	3256
lime	1635	conglomerate	3263
red rock	1640	siliceous lime	3285 T.D.
shale	1675		
lime	1720		
red rock	1735		
lime	1742		
shale blue	1748		
lime	1770		
red rock	1780		
lime	1850		
red rock	1865		
lime	1905		
shale blue	1920		
lime	1925		
shale light	1940		
Hole caving.			
lime	1945		
shale light	1955		
lime	2030		
shells	2045		
shale blue	2070		
hole caving.			
lime	2095		
shale	2110		