


GULF OIL CORP.
H.B. Schroeder No. 4

SEC. 20 T. 17 R. 9W.
NW SE SW
1220' SL 1350' WL SW $\frac{1}{4}$

Total Depth. 3224
Comm. 7-19-40 Comp. 8-7-40
Shot or Treated.
Contractor.
Issued. 10-12-40

County Ellsworth.



CASING.

85/8" 200'
5 1/2" 3221'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations. no wtr. Sonic Motor.

surface clay and sand	95
shale grey	204
red bed and shells	430
anhydrite	470
red bed and shells	510
red bed	530
shale blue and shells	890
shale blk and shells	930
salt	1175
anhydrite blk shalo & shells	1310
shalo blue and limo	1375
shale blue and lime shells	1550
limo and shalo breaks	1580
limo and shalo breaks	1635
limo chort and shale blue	1670
limo and blue shale	1745
limo and shale	1935
limo and shalo breaks	2050
limo and shale	2125
shalo and limo shells	2212
limo and blue shale breaks	2415
limo and shale	2488
limo and blue shale	2530
limo and hard shalo	2563
brokon limo	2570
limo	2612
limo and blue shale breaks	2620
limo	2653
limo	2782
shale blk with limo shells	2840
limo	2900
shalo and limo shells	2910
limo and blue shale	2942
limo and shale	2967
sdv limo Oil stain	3003
limo	3180
limy shalo	3190
limo and shalo breaks	3204
shalo blk and lime	3219
sand	3220
Arbucklo dolomite	3221
limo	3224

Total Depth.

Arbucklo lime 3220-3224.