

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

API No. 15 — 053 — 20,394
County Number

Operator
R. M. Edwards

Address 2530 Russell Parkway Great Bend, Kansas

Well No. #3 Lease Name Dees


Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Woodman & Iannitti Geologist

Spud Date 12-18-74 Total Depth 3220 P.B.T.D.

Date Completed 12-30-74 Oil Purchaser Phillips

S. 23 T. 17 R. 9 E W
Loc. C NW NW
County Ellsworth



Elev.: Gr. 1768

DF 1770 KB 1773

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28#	291	Reg	150	3% Cal Chloride
Production	7 7/8	5 1/2	14#	3219	Poz	100	Dalt Sat CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Kone	3180-81

TUBING RECORD

Size	Setting depth	Packer set at
2 1/2	1517	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 Gal. NE 15% acid	3180-81

INITIAL PRODUCTION

Date of first production <u>Swab Test 4 hrs</u>		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil <u>5 BOPH tr. wtr bbls.</u>	Gas <u>MCF</u>	Water <u>bbls.</u>	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s) <u>3180-81</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

R. M. Edwards

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Oil

Well No.

3

Lease Name

Dees

S 23 T 17 R 9 EX W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DRESSER ATLAS LOG				
Severy Shale	2424 (- 651)			
Topeka	2456 (- 683)			
Heebner	2718 (- 945)			
Bn Lime	2836 (-1063)			
Lansing	2854 (-1081)			
Arbuckle	3176 (-1403)			
TD	3220 (-1447)			
DST 2420-2470 (30-30-30) Rec. 360' thin drlg mud. IFP 20-78 XXXXXXXXXXXX ICIP 794 FFP 87-195 FBHP 709				
DST 2855-2905 (30-30) Rec. 40' drlg mud IFP 37 - 37 BHP 62				
DST 3035-3060 (30-30) Rec. 30' drlg mud IFP 24-27 BHP 107 Test was dead in 26 min.				
DST 3188-3194 (30-30-30-30) Rec. 700' gas in pipe, 2400' formation wtr. slightly oil cut. IFP 361-912 ICIP 1054 FFP 928-1046 FCIP 1054				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Marvin Muller

 Signature
 Production Superintendent

 Title
 January 15, 1975

 Date

State Geological Survey
WICHITA, BRANCH

REG. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

23-17-9W

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

API# 15-053-20,394


1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

December 31, 1974

Company; R. M. Edwards
Farm; #3 Dees
Location; C NW NW
Section; 23-17S-9W
County; Ellsworth
Contractor; Woodman & Iannitti Drilling Co.
Comm; December 18, 1974
Compl; December 30, 1974
Total Depth; 3220'
Casing; 8 5/8" @ 291.18' w/150 sacks
5 1/2" @ 3219' w/100 sacks

Figures Indicate Bottom Of Formations:

80	Shale & Clay
250	Sand
291	Shale
425	Shale
570	Red Bed
677	Red Bed
710	Anhy
1250	Shale
1570	Shale & Lime
2250	Lime
2455	Lime & Shale
2535	Lime
2620	Lime & Shale
2755	Lime
2905	Lime
3005	Lime
3150	Lime
3180	Lime
3220	Arbuckle



I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman