

plotted by J. H.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
Union National Bank Bldg, Wichita, Kansas.


ARTER OIL CO., COMMUNITY.  
B. Groth No. 3

SEC. 23 - T. 17 - R. 9W  
Cen SW  $\frac{1}{4}$   
1320' fr S.L.  
1380' fr WL. SW  $\frac{1}{4}$

AUG 22 1936

County - Ellsworth.

Total Depth. 3187  
Comm. - 6-6-36 Comp. 6-29-36  
Shot or Treated.  
Contractor. Parker Drilling Co.  
Issued. 6-22-36



CASING.

103/4" 204 7" 3183'

Elevation.

Production. Pot. 1365 B.  
15 water 22 hrs.

Figures Indicate Bottom of Formations.

cellar	7
soil and clay	70
sand	85
shale and shells	208
shale and shells	873
shale and shells	920
salt	1065
salt and shale	1140
shale and lime shells	1195
lime and shale	1292
lime	1312
shale and shells	1363
broken lime and shale	1440
lime and shale	1530
lime and sand	1560
broken lime and shale	1630
shale and lime	1676
shale and shells	1818
shale and shells	2063
shale and lime	2148
shale and shells	2240
lime and shale	2292
broken lime	2340
lime	2380
broken lime and shale	2458
broken lime	2498
lime	2647
broken lime	2692
lime	2774
lime	2807
shale and shells	2862
shale and lime	2923
broken lime	2935
show oil 2923-35	
lime	3038
lime	3160
lime and shale	3171
shale green	3183
dolomite	3187 Total Depth

3150' oil in 2 hours.  
Pump 785 B. O. no water.  
Pump 1365 bbls oil and 15 bbls wtr.