

Noted by C. A. P.

PHILLIPS PETROLEUM CO.
 Melchert No. 6


SEC 23 T. 17 R. 9W
 SW SE NE

Total Depth. 3210'
 Comm. 1-30-36 Comp. 3-5-36
 Shot or Treated.
 Contractor. Mac & Stauffer
 Issued. 4-11-36

County. Ellsworth

APR 11 1936

CASING.
 12 1/2" 455'
 7 " 3201'



Elevation.

Production. Pot. 1315 Bbls.
 oil.

Figures Indicate Bottom of Formations.

surface	170
shale & shells	1015
shale & salt	1175
lime & salt	1287
lime	1389
shale & lime	1436
shale	1490
lime	1555
lime & shale	1652
shale	1779
broken lime & shale	1800
shale	1810
broken lime & shale	1880
shale & lime	1950
shale	2047
broken lime & shale	2085
shale	2210
lime	2280
shale	2375
lime	2838
shale	2840
lime	3134
shale	3199
lime 3202 equals 3205	
S.L. correction	
lime	3210
Total Depth	