

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY:
Union National Bank Bldg, Wichita, Kansas.

CARTER OIL CO.-SHELL PETRO.
C.C. Ogden No. 1

SEC. 26 T. 17 R. 9W.
NEc SW
440' NL 440' EL.

Total Depth. 3187
Comm. 5-5-35 Comp. 6-26-35.
Shot or Treated.
Contractor.
Issued. 8-3-35

County. Ellsworth.

CASING.

13" 125'
103/4" 381'
85/8" 2000'
UR 2580' UR 3028



Elevation.

Production. Pump 715 B. 24H.

Figures Indicate Bottom of Formations.

Potential.

lime	5	broken lime	1490	3 1/2 BWPHR 2420-26	
sand	125	lime	1505	lime	2560
red rock	135	broken lime	1520	shzle	2570
shale	145	lime	1555	lime	2573
lime	165	2 BWH1520		2575 equals 2580 SLC	
shale	190	3 BWPH 1540		lime	2615
shale	240	shale	1560	shale.	2618
HFW 240		lime	1575	lime	2630
sand	270	shale	1600	shale	2632
sand	280	lime	1625	lime	2640
pyrite	289	shale	1635	broken lime	2678
sand	295	lime	1675	lime	2715
lime	299	shale	1680	1 BWPH 2710	
shale	305	lime	1750	shale	2718
shale	350	shale	1770	lime	2725
sand	365	lime	1800	shale	2735
lime	370	lime	1820	lime	2777
shale	395	shale	1825	broken lime	2787
395 equals 381 SLC		lime	1855	lime and shale	2810
red rock	445	lime	1890	lime	2817
lime	451	shale	1920	shale	2841
red rock	495	lime	1930	lime	2843
shale	540	shale	1940	shale	2850
red rock	600	lime	1945	2850 equals 2847 SLC	
sdv shale	615	shale	1955	lime	2867
shale red	660	lime	1980	lime	2875
shale	720	shale	2000	broken lime	2893
shale	900	lime	2005	lime hard	2900
salt	930	shale	2020	broken lime	2905
shale	960	lime	2030	lime	2925
salt	990	red rock	2050	lime hard	2950
shale	1015	lime	2060	lime soft	2958
salt	1060	shale	2100	lime hard	2960
shale	1070	shale	2110	lime soft	2970
salt	1135	lime	2115	lime hard	2975
shale	1145	shale	2145	lime	2990
shale	1160	lime	2155	lime	3028
lime	1190	shale	2165	broken lime	3050
shale	1215	lime	2170	lime	3070
lime	1230	shale	2190	shale	3080
shale	1240	lime	2195	lime	3125
lime	1265	shale	2205	dolomite	3187
broken lime	1290	lime	2230	Total Depth.	
lime	1298	shale	2255		
broken lime	1304	lime	2285	Pay 3181 1/2-3187	
lime	1315	shale	2295	3150' oil 10 hrs.	
lime	1340	lime	2300	Swab 80 bbls oil 2 hrs	
shale	1345	shale	2350	6-26-35.	
lime	1375	lime	2380	6-28-35 Pump 715 B.	
red rock	1385	shale	2384	24 hr Pot.	
lime	1390	lime	2404	6-29-35 Pump 487 B.	
shale	1400	lime	2410	no wtr 5 1/2 hrs.	
lime	1425	shale	2420		
shale	1435	lime	2425		
lime	1455	lime	2545		
shale	1470	shale	2555		