


THE CARTER OIL CO.  
Ogden No. 8A

SEC. 26 T. 17 R. 9W  
NW SW SW  
990' fr S & 330' fr WL

County. Ellsworth

Total Depth. 3181'  
Comm. 2-16-37 Comp. 3-25-37  
Shot or Treated, 1000 G. 3168-81 3-25-37  
Contractor. Mac & Stauffer  
Issued. 4-17-37 Rotary O-3168  
Cable 3168-81



CASING.  
10" 218'  
7" 3166'

Elevation.

Production. Pot. 935 B.

Figures Indicate Bottom of Formations.

shale, shells	120
sand rock, lime shells	214
lime, shells	370
shale, lime streaks	555
shale, lime shells	615
shale, shells	790
shale	890
salt	1120
shale	1180
lime shells	1300
shale	1385
shale, lime shells	1465
shale	1505
lime	1590
brkn lime	1655
shale, lime shells	1760
brkn lime	1820
shale	2390
lime	2835
shale	2858
lime	3000
shale	3065
lime	3160
shale green (cored)	3166
lime (cored)	3169
sd lime	3179
lime	<del>3180</del> 3181
Total Depth.	

Siliceous 3168-3181

1st show 3176

Test before acid 3-24-37, 182 bbls. in 12 hrs.

Potential 3-28-37, 935 bbls.

*Com. By Bureau*  
4-17-37  
4-24-37