


CARTER OIL CO. (COMMUNITY)  
 H.G. Teubner No. 8.

SEC. 26 T. 17 R. 9W  
 CWL NW $\frac{1}{4}$   
 1320' fr NL; 440' fr WL NW $\frac{1}{4}$

County. Ellsworth

Total Depth. 3190'  
 Comm. 8-20-36 Comp. 9-25-36  
 Shot or Treated. 1000 Gals. Acid.  
 Contractor.  
 Issued. 10-24-36



CASING:  
 10 $\frac{3}{4}$ " 213'  
 7 " 3168'

Elevation.

Production. Pot. 455 B.  
 No water.

Figures Indicate Bottom of Formations.

sand & shells	195
sand	215
shale	320
shale & shells	440
anhydrite	460
shale & shells	620
shale	900
shale & salt	1115
salt	1195
lime	1225
shale & lime	1250
shale	1270
lime	1310
shale	1540
lime	1575
SLC 1575-1545	
lime	1605
lime & shale	1695
lime	1850
shale	1900
lime	1920
shale	2380
lime	2420
shale	2440
lime	2545
lime	2745
shale	2855
lime	2912
shale	2920
lime	2985
brkn lime	3053
lime	3120
shale	3150
lime	3152
brkn lime & shale	3166
brkn lime	3168
shale	3169
dolomite	3170
dolomite	3190
Total Depth.	

750' oil in hole at 3181  
 1850' oil in hole at 3188  
 3100' oil 3186-88