


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

THE CARTER OIL CO. -Community
A. Groth No. 3

SEC.27 T. 17 R. 9W
C SE NE SE

Total Depth. 3159'
Comm. 2-11-37 Comp. 3-7-37
Shot or Treated. 1000 Gals.
Contractor. Cotal Drig.Co.
Issued. 3-27-37

County. Ellsworth



Elevation.

CASING: Rotary 3150
Cable 3150-59
10" 218'
7" 3150'

Production. Pot.1538 B.
21 hrs.
No water.

Figures Indicate Bottom of Formations.

cellar	10
shale, shells	100
shy shale, shells	220
shale, shells	910
salt	1100
shale, shells	1235
lime	1258
brkn lime	1313
lime	1345
shale, lime shells	1493
lime hrd	1565
brkn lime	1585
lime	1671
lime, pig iron	1705
shale, lime shells	1861
brkn lime	1915
shale, lime shells	2340
lime	2360
shale, lime shells	2385
lime	2400
shale, lime shells	2437
lime	2464
brkn lime	2510
lime	2689
shale, lime shells	2808
shale	2830
lime	2940
shale	2950
lime	2978
brkn lime	2985
shale, lime shells	3010
lime	3150
cored lime	3153
lime	3159
Total Depth.	

Siliceous Lime Top 3147-3159

Previous to potential, well made
278 oil and no water in 9 hrs.

Show Oil 3028-38
slight show oil 3150-53
1350' oil 3158'
1750' oil 3159'