


CITIES SERVICE OIL CO.
Mollhagen No. 2-C.

SEC. 29 T.17 R.9W
NW 1/4 SE
440' S 440' E Center

County. Ellsworth

Total Depth. 3325'
Comm. 5-4-40 Comp. 5-30-40
Shot or Treated.
Contractor. R.W.Rine Drlg.Co.
Issued. 6-29-40



CASING:
8 5/8" @ 208'
5 1/2" @ 3325'

Elevation.

Production. Dry-to be used
for wtr disposal

Figures Indicate Bottom of Formations.

sand & red rock	120
shale & shells	440
red rock	500
red rock & shale	816
shale red&blue & shells	970
salt	1170
shale & shells	1455
lime	1475
shale & shells	1595
shale & lime	1990
shale	2004
shale & shells	2290
shale	2436
shale & lime	2575
lime	2780
shale & shells	2836
shale & lime	2937
lime	3022
shale & lime	3169
lime	3240
cored sand & shale (rec. 4')	3246
shale & lime	3249
cored shale & lime (rec. 3')	3257
lime	3294
lime, shale, chert	3325
Total Depth.	

Top Lansing 2910
Top Erosional Arbuckle 3248
Top Arbuckle 3253
Penetration 72

Halliburton drill stem test
3253-59, packer at 3253,
1350' mud in 45 min.