

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company - CITIES SERVICE OIL CO. ET AL
Farm - Schroeder "A" No. 14

SEC. 29 T. 17 R. 9W
NW NW NW
280' S, 280' E of NWc

Total Depth. 3218'
Comm. 9-27-48 Comp. 10-16-48
Shot or Treated.
Contractor. Herndon Drlg.
Issued. 12-4-48

County. Ellsworth
KANSAS



CASING:

8 5/8" 282' cem w/150 sx.
5 1/2" 3202' cem w/150 sx.

Elevation. _____

Production. Pmpd. 101 Oil, 25
water, 24 hrs.

Figures Indicate Bottom of Formations.

shale and sand	150
shale and shells	282
red bed	450
shale and sand	750
shale	825
shale and shells	1645
lime and shale	2080
shale	2485
lime and shale	2570
lime	2815
shale	2870
lime RTD	3205
3205 RTD = 3203 SLM	
lime	3218
total depth	

Tops:

Corr. Lansing	2878
Corr. Simpson	3200
Corr. Arbuckle	3201

Penetration 17'

Fillup:

140' oil in 1 hrs. 50 min.
610' oil in 2 hrs. 50 min.
1090' oil in 3 hrs. 50 mins.
1350' oil in 9 hrs. 50 mins.
1580' oil in 12 hrs. 50 mins.
1820' oil in 18 hrs. 25 mins.