


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company- B & R DRILLING CO.
 Farm- Schroeder No. 1

SEC. 31 T. 17 R. 9W
 SE SE SE

Total Depth. 3273
 Comm. 10-25-51 Comp. 11-8-51
 Shot or Treated.
 Contractor.
 Issued. 1-26-52

County Ellsworth
 KANSAS



Elevation. 1747

Production. Dry

CASING:

10 3/4" 183' cem. w/125 sx.
 7" 3222 cem. w/50 sx.

Figures indicate Bottom of Formations.

surface hole	183
shale, shells	249
iron	254
shale	274
iron, shale	300
red bed	390
shale, shells	450
anhyd.	488
shale, shells, redbed	516
shale, shells	540
shale	594
shale, shells	970
shale, salt	1170
shale, anhyd.	1220
shale, shells	1381
shale, anhyd.	1420
shale, salt	1495
shale, shells	1547
lime	1623
lime, shale	1715
lime	1745
lime, shale	2604
lime	2780
shale, lime	2860
lime	2985
lime K.C.	3030
lime	3195
congl.	3222
lime	3228
lime	3238
Total Depth	
Tops: Scout	
Lansing	2878
Arb.	3221