


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company DERBY OIL CO.
Farm Colberg No. 3

SEC. 33 T. 17 R. 9 W
SW NW SW

Total Depth. 3243'
Comm. 7-20-46 Comp. 8-3-46
Shot or Treated.
Contractor. G. W. Reel
Issued. 9-14-46

County. Ellsworth
KANSAS



CASING:
8 5/8" 257' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

clay & sand	0-50
shale, shells & sand	168
shale	421
anhydrite	444
shale & shells	917
shale & salt	1123
anhydrite & shale	1168
anhydrite brkn & shale	1330
shale & lime strks	1435
lime	1437
shale & lime	1521
cherty lime	1537
lime	1578
lime & shale strks	1768
lime brkn & shale	1884
shale & lime	2168
lime w/shale strks	2191
lime & shale	2439
shale	2475
lime	2560
lime w/shale strks	2622
lime	2754
shale & lime	2859
lime	2870
lime & shale	2890
lime	2980
lime sft	2998
lime	3223
shale & lime	3234
lime	3243
Total Depth.	

Tops:
Lansing 2879
Arbuckle 3233

No shows

Plugging Record:

Wooden plug & rock bridge
@ 250' w/15 sx. cem. on
top then mud to 40'. Wooden
plug & rock bridge @ 40 &
5 sx. cement to 5' from
surface.