


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- STERLING DRILLING COMPANY ET AL  
 Farm- Schlick No. 1

SEC. 33 T. 17 R. 9W  
 NW SW SE

Total Depth. 3500'  
 Comm. 3-19-59 Comp. 4-7-59  
 Shot or Treated.  
 Contractor, Sterling Drlg. Co.  
 Issued. 7-25-59

County Ellsworth  
 KANSAS



CASING:  
 8 5/8" 243' cem w/165 sx.  
 5 1/2" 3315' cem w/100 sx.

Elevation. 1754' RB

Production. 76 BOPD

Figures Indicate Bottom of Formations.

shale & sand	65
shale	250
shale & red bed	780
shale & lime	1630
lime	1765
shale & shells	1960
shale	2460
lime	2775
shale	2846
lime	3205
shale	3235
Arbuckle lime	3500 RTD
Total Depth	

TOPS: SCOUT  
 Lansing 2867  
 Arbuckle 3231

Perf. w/4 jet shots per foot from 3237-3240.  
 Acidized w/250 gal. M.C.A. @ 350# by B. J.  
 Well Service.