


THE CARTER OIL CO.
 Elizabeth No. 1.

SEQ. 34 T. 17 R. 9W
 NE₀ NE
 330' fr N & E Lines NE $\frac{1}{4}$

County. Ellsworth.

Total Depth. 3186'
 Comm. 11-25-36 Comp. 12-17-36
 Shot or Treated. 1000, 1000, 1000 Gals.
 Contractor. Parker Drlg. Co.
 Issued. 1-30-37 Rotary O-3169
 Cable 3169-3186



CASING:
 10" 205'
 7" 3165'

◆ Elevation.

Production, Pot. 1147 B.

Figures Indicate Bottom of Formations.

cellar	10
surface	50
shale, lime shells	115
sticky shale	120
red bed, shale	175
sandstone, shells	180
shale	200
shale, lime shells	215
shale, shells	320
red bed	375
shale, shells	870
salt	1115
shale, shells	1290
brkn lime	1300
shale	1330
shale, shells	1490
sand	1520
shale	1610
shale, shells	1675
brkn lime	1770
shale, shells	1805
shale	1864
shale, shells	2255
shale	2350
brkn lime	2420
shale	2440
lime	2700
brkn lime	2760
shale, shells	2783
shale	2832
brkn lime	2850
shale	2865
brkn lime	2890
lime	2920
lime, shale	2935
lime hrd	2952
lime sft	2962
lime hrd	2970
lime	3140
lime, shale	3160
brkn lime	3172 (Top of Siliceous 3166)
cored lime	3175
lime, shale	3179
lime	3186
Total Depth,	

At 825# would not take
 Acidized with 1000 gals. 3168-73 12-21-36
 Acidized with 1000 gals. 3168-73 12-29-36 no good
 Acidized with 1000 gals. 3168-73 1-10-37 O.K @ 1200#

Siliceous lime 3166-3186