


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BENNETT & ROBERTS DRILLING CO.
Farm. Mollhagen No. 1

SEC. 35 T. 17 R. 9W
C NW/4

Total Depth. 3186
Comm. 12-1-55 Comp. 12-9-55
Shot or Treated.
Contractor. Bennett & Roberts Drilling Co.
Issued. 2-4-56

County Ellsworth
KANSAS



CASING:
8 5/8 @ 184' w/ 125 sx cmt.
5 1/2 @ 3180' w/ 100 sx cmt.

Elevation. 1764 DF

Production. 25 BOPD

Figures Indicate Bottom of Formations.

surface soil & clay	10
shale, sand & rock	110
red bed & shale	200
blue shale	350
red bed	540
shale & shells	845
anhydrite	885
red bed & shale	1100
shale & lime streaks	1365
shale & broken lime	1490
lime	1570
shale & lime	2890
lime	3186
Total Depth	

Cimarron anhydrite	845
Heebner	2709
Toronto	2731
Douglas shale	2743
Brown lime	2826
Lansing-K. C.	2849
Base K. C.	3100
Conglomerate	3172
Arbuckle	3180

All RB Meas.

No electric logs run

No cores.

DST #1: 3180-86, open 1 hr. strong
bl. sl. dimin. end of 60 min. rec.
540' gas in pipe, 240' free oil, 330'
muddy gassy oil, 60' brackish wtr.
IFP 50#, FFP 250#, BHP 1020#/20 min.