

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY:  
 Union National Bk Bldg, Wichita, Kansas.


CARTER OIL CO: -COMMUNITY  
 C. O. Ogden No. "A" 4

SEC 26 T. 17 R. 9 W  
 CSL SW  
 440' fr SL 1320' fr EL SW<sup>1</sup>/<sub>4</sub>

DEEPENING RECORD

Total Depth. 3643'  
 Comm. 4-19-36 Comp. 5-12-36  
 Shot or Treated. 1000 gal acid  
 Contractor. E. Shaeffer  
 Issued. 6-5-43

County. Ellsworth



CASING:

103/4 219' 7" 3176'

Elevation.

Production. Pot. 1251 B.

Figures Indicate Bottom of Formations.

cellar	8	lime	3114
surface	20	lime and shale	3167
red rock and shale	90	lime	3175
sand	110	shale green	3178
shale and shells	170	dolomite	3180
shale and shells	214	dolomite	3182
lime and shale	225	Total Depth.	
lime and shale	700	200' oil	
shale and shells	900	increased to 600' oil in 10 hours.	
salt	1087	1600' oil 3 hours	
salt	1125	Pump 285 bbls oil and no water 15 hrs.	
shale and shells	1275	Pump 770 bbls oil and no water	
lime and shale	1400	15 hours. Start potential Pump 1251	
red rock and lime	1475	oil and no water 24 hours.	
shale and shells	1550		
lime and shale	1634		
red rock and lime shells	1698		
lime	1741		
lime and shale	1824		
shale and shells	1900		
shale	2000		
lime	2030		
shale and shells	2095		
shale	2110		
lime and shale	2240		
shale and shells	2280		
lime and shale	2345		
shale and lime	2417		
shale and shells	2455		
lime	2740		
shale	2825		
shale	2831		
lime	2936		
lime and shale	2990		
shale and lime	3049		

DEEPENING RECORD:

Phillips Petro. Co.  
 Comm. 1-1-43 Comp. 2-12-43  
 Salt Wtr Disposal Well

lime cored	3202
lime	3215
lime brkn	3222
lime	3316
lime sdy	3326
lime hd	3391
shale green	3394
lime	3566
sand	3596
hrd from 3590-96	
sand	3623
sand hd	3626
sand	3643
Total Depth.	

Tops: Simpson 3173  
 Arbuckle 3178  
 Basal Sd? 3626