

48841

CARTER OIL CO.-COMMUNITY
Elizabeth No. 3

DEEPENING RECORD

SEC. 34 T. 17 R. 9W.
CN/2 NE
660' fr NL 1320' fr EL NE $\frac{1}{4}$

Total Depth. 3334'
Comm. 2-19-37 Comp. 3-16-37
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 12-10-38

County Ellsworth.



CASING.

103/4" 206' 7" 3179'

Elevation.

Production. Temp. Aird.

Figures Indicate Bottom of Formations.

cellar	7
surface	50
sand	85
clay	190
shale and shells	215
shale and shells	330
red rock & shale	420
red rock	560
shale and shells	890
salt	1005
salt and shale	1090
shale and shells	1498
sand	1528
shale and shells	1610
broken lime	1678
shale and lime	1755
shale and shells	1920
broken lime & shale	1930
lime	1950
broken lime & shale	2020
shale and lime shells	2099
shale and shells	2152
broken lime	2170
broken lime & shale	2190
lime	2202
broken lime & shale	2310
shale and shells	2355
lime	2419
sand	2440
broken lime and shale	2490
lime	2569
lime	2576
broken lime	2585
lime	2775
broken lime & shale	2860
lime	2885
broken lime & shale	2890
lime	2950
shale	2970
lime	3005
broken lime & shale	3015

lime	3065
lime	3145
broken lime & shale	3165
conglomerate	3178
lime	3200

Total Depth.

very slight Rainbow show oil 3188-89
100' fluid in $\frac{1}{2}$ hr 3192-95
500' water 3196
HFW 3200

DEEPENING RECORD

Comm. 5-2-38 Comp. 6-5-38
Production. Salt Wtr Disp.

dolomite 3200-3334

Total Depth.