

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

6-18-10W

GULF OIL CORP.
B.F. Stout No. 5.

SEC. 6 T. 18 R. 10W
CS $\frac{1}{2}$ NW NE

Total Depth. 3230'
Comm. 1-31-40 Comp. 2-22-40
Shot or Treated.
Contractor.
Issued. 4-6-40

County. Rice



CASING:
8 5/8" 211'
5 1/2" 3225'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations. No wtr, Sonic Meter

cellar	8
sand & gravel	85
clay	100
shale & sand shells	220
sand	240
shale & shells	350
red bed	495
shale & shells	660
shale & anhydrite	695
shale & shells	1050
salt & shells	1195
shale & shells	1430
sand	1455
lime brkn	1600
shale & shells	1630
lime	1652
shale & lime	1772
lime brkn	1860
shale	1918
shale & lime	1990
shale & shells	2325
lime brkn	2430
lime	2454
shale & shells	2538
shale & lime	2590
lime Topeka	2670
lime	2726
lime Topeka	2755
lime Topeka hrd	2788
lime Topeka	2842
shale	2845
shale & shells	2928
shale	2958
lime K.C.	3017
lime K.C. oored	3025
lime brkn	3089
shale & lime	3144
lime	3187
lime K.C. brkn	3217
lime brkn	3225
lime oored	3230
Total Depth.	

Arbuckle lime 3225-3230