


GULF OIL CORP.
B. F. Stout No. 6.

SEC. 6 T. 18 R. 10W
CN $\frac{1}{2}$ NW NE

Total Depth. 3229'
Comm. 2-21-40 Comp. 3-28-40
Shot or Treated.
Contractor.
Issued. 4-20-40

County. Rice



CASING:
8 5/8" 259'
5 1/2" 3224'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations. Depthograph, no wtr

sand & shale	92
shale & shells	259
shale & red bed	365
red rock	590
shale	770
anhydrite	800
shale & shells	910
shale	1010
shale & shells	1120
salt	1141
shale & shells	1255
shale & lime	1387
lime brkn	1470
shale & lime	1645
lime	1695
shale & lime	1770
lime brkn	1832
lime	1850
shale & shells	1980
shale & lime	2068
lime brkn	2118
shale & lime	2174
lime, shells, shale	2250
shale & shells	2320
shale & lime	2429
shale & shells	2601
lime Topeka	2650
lime	2798
lime Topeka	2815
shale & shells	2880
shale & lime	2930
lime	2981
lime K.C.	3034
lime	3044
lime brkn	3077
lime	3106
shale	3138
lime	3195
lime brkn	3206
shale	3224
lime	3229

Total

Top Oswald 2948
Anbuckle Lime 3223-29

Top
Arb