

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg, Wichita, Kansas.

SLICK PRYOR AND LOCKHART.
Moran No. 2


SEC. 4 T. 18 R. 10W.
NW SW NW

Total Depth. 3271
Comm. 12-23-35 Comp. 2-4-36
Shot or Treated.
Contractor. Allison-Fitzwilliams.
Issued. 4-4-36

County. Rice.

CASING.

20"	245'	8 1/4"	2827'	2941'
15 1/2"	510'	65/8"	3238'	
13"	969'	UR 1038'	53/16"	3262'
10"	1763'			



Sec. T.
T. Sil. 3246

Elevation. 1785

Production Pot. 738 R.

Figures Indicate Bottom of Formations.

cellar	14	lime	1675	shale	2510
clay yellow	20	lime	1710	shale	2515
clay yellow	50	shale	1725	lime	2520
water sand	60	lime	1730	shale	2535
water sand	70	shale	1740	lime	2545
red rock	105	shale	1750	1BW 2640-50	
shale blue	140	lime	1775	lime	2790
shale grey	160	red rock	1790	red rock	2795
shale	185	red rock	1795	lime	2805
water sand	200	lime	1805	shale	2815
shale	210	shale	1825	shale	2817
sand	220	lime	1850	show gas	
shale dark	236	lime	1855	lime	2825
shale blue	260	red rock	1875	lime	2830
mud blue	275	lime	1885	shale	2843
shale blue	310	red rock	1900	sand	2850
red rock	380	lime	1920	shale	2860
red rock	510	shale	1925	broken lime&shale	2895
anhydrite	525	lime	1930	shale	2910
red rock	580	shale blue	1950	lime	2915
red rock	750	shale blue	1960	shale	2927
shale grey	760	lime	1985	lime	2930
shale grey	820	shale blue	1990	lime	2970
red rock	855	lime	2000	lime	3085
red rock	865	lime	2010	show oil 3070 1BW	
shale blue	905	red rock	2015	shale	3090
shale blue	965	lime	2020	lime	3100
salt	969	shale grey	2030	lime	3130
salt	1235	shale	2045	2 BW 3070	
shale grey	1250	lime	2050	lime	3180
salt	1260	shale blue	2065	shale	3185
shale grey	1275	shale blue	2075	lime	3203
lime	1280	shale	2080	red rock	3205
shale grey	1290	lime	2085	shale blue	3209
lime	1315	shale blue	2125	lime broken	3213
lime	1320	lime	2130	V.C. shale	3218
shale grey	1330	shale blue	2150	conglomerate	3224
lime shells	1365	shale blue	2160	chert&lime	3230
lime	1375	lime	2170	chert	3242
shale grey	1385	shale blue	2180	shale green	3245
lime	1405	shale	2245	chert	3248
shale grey	1430	lime	2260	lime	3251
shale grey	1435	shale blue	2280	Top Sil lime showed free	
lime	1460	shale blue	2305	oil 3248-51	
red rock	1480	lime	2320	lime	3271