


TRANSWESTERN OIL CO. ET AL  
 Moran No. 6-A.

SEC. 4 T.18 R.10W  
 NW NW NW

Total Depth. 3268'  
 Comm. 8-25-38 Comp. 9-14-38  
 Shot or Treated.  
 Contractor. Springrose Drlg.Co.  
 Issued. 11-12-38

County. Rice



CASING:

13 3/8" 235'  
 8 5/8" 3237'

Elevation. 1776

Production. Pot. 299 B.

Figures Indicate Bottom of Formations.

surface	125
shale & shells	235
shale & lime	490
red rock & shale	760
shale & shells	1015
salt	1195
lime & shale	1295
shale	1320
brkn lime	1375
lime	1415
shale	1485
lime	1510
breaks lime	1590
sand	1615
lime	1810
shells	1870
lime	1885
lime & shale	2035
shale	2250
lime	2260
shale	2330
lime & shale	2465
lime	2475
shale	2550
lime	2570
shale	2590
lime	2825
shale	2840
breaks lime	2895
lime	2915
shale & shells	2940
shale & lime	2975
lime	3030
breaks lime	3050
lime	3070
lime & shale	3120
lime	3252
Siliceous lime	3268
Total Depth.	

3252  
 1776  
 - 1476

Oil 3264-67 & wtr 3267-68  
 1 bbl fluid per hr W/3% wtr  
 before acid.  
 Filled 350' in 12 hrs.