

BRIDGEPORT MACHINE CO.
Habiger No. #. 5

SEC. 5 T. 18 R. 10W
SE NW NW

Total Depth. 3019'


Comm. 3-1-38 Comp. 4-14-38

Shot or Treated. 6000 Gals.

Contractor. Bridgeport Machine Co.

Issued. 5-7-38

County. Rice



CASING:

15 1/2" 72'
13 3/8" 539'
10 " 1870'
8 1/4" 2274'
7 " 3007'

Elevation. 1789

Production. Pot. 3578.28 B.

Figures Indicate Bottom of Formations.

cellar	12	lime	1915
yellow clay	55	shale	1920
sand HFW 55-60	60	lime	1945
shale yellow	100	red rock	1950
red rock	110	lime 1BW 1955-60	1980
shale blue	130	shale	1985
sand HFW 130-40	230	lime	2025
clay blue	295	shale blue	2040
shale grey	300	lime	2050
clay blue	315	shale blue	2080
red rock	535	lime	2105
anhydrite lime	552	slate & lime	2140
shale grey	555	red rock	2150
red rock	630	lime 2BWPH 2165	2195
shale	640	shale 2 BW 2190	2205
red rock	765	lime	2215
shale grey	775	shale	2240
lime	785	lime	2260
shale grey	805	shale blue	2310
shale	835	lime	2335
red rock	875	shale blue	2345
shale	885	shale grey	2360
clay blue	935	lime	2375
shale grey	975	shale	2390
lime	980	lime	2410
shale	985	brkn lime	2430
salt	1235	shale	2455
clay blue	1280	lime	2505
lime	1285	shale	2510
shale	1290	lime	2530
lime	1300	shale grey	2535
shale	1305	lime 1 BW 2610	2635
lime	1325	shale	2640
shale	1335	lime	2800
lime	1345	shale	2805
shale	1350	lime	2825
lime	1415	gas at 2735 gas at 2825	
shale grey	1425	shale lgt	2840
lime	1470	more gas at 2835	
red rock	1485	shale	2875
lime	1525	shale sdy	2910
shale blue	1530	lime	2915
lime 2 BW 1505-10	1655	shale drk	2920
shale blue	1675	shale	2925
lime 8 BW 1605	1700	lime	2987
shale	1705	shale grey	2992
lime	1710	lime	2997
red rock	1720	shale	3007
lime	1740	lime	3019
shale drk	1750	Total Depth.	
lime	1775		
red rock	1780		
lime	1805		
red rock	1810		
lime	1845		
red rock	1860		

2920
1789
1131