


TRANSWESTERN OIL CO.
 J.E. Roesler No. 3.

SEC. 5 T.18 R.10W
 CWL NW SE

Total Depth: 3236'6" = 3240' SLC
 Comm. 3-23-40 Comp. 4-23-40
 Shot or Treated.
 Contractor.
 Issued. 6-22-40

County. Rice



CASING:
 10" 210'
 7" 3224'

Elevation.

Production. Pot. 802 B.

Figures Indicate Bottom of Formations.

clay	30
sand & red rock	105
clay, sand & shells	220
shale blue	265
shale & red bed	431
red bed	508
anhydrite & lime	535
red bed, shale, shells	775
shale	875
salt	960
salt, shale, shells	1143
salt, shale, lime	1273
lime & shale brks	1400
lime w/shale brks	1515
shale & shells	1640
lime	1910
shale & lime	2020
lime & shale brks	2110
lime brkn	2190
shale & lime	2275
lime brkn	2330
shale & lime	2440
shale & shells	2460
lime	2735
shale	2743
lime	2760
shale & lime	2811
lime w/brks	2870
lime	2941
shale & lime	2976
lime & brks	3039
lime K.C.	3082
lime w/brks	3132
lime	3155
lime brkn	3202
lime	3204
conglomerate	3223
lime Arbuckle-sh oil	3225
dolomite wh cryst	3232
dolomite wh, lgt gy cryst	
cryst.	3236'6"
3236'6" equals 3240 SLCorr.	
Total Depth.	