


GULF OIL CORP.
 Wilbur R. Ames No. 1.

SEC. 6 T. 18 R. 10W
 NWc NW
 408' S 330' E NWcor.

Total Depth. 3244 $\frac{1}{2}$ '
 Comm. 9-20-38 Comp. 10-18-38
 Shot or Treated.
 Contractor.
 Issued. 12-3-38

County. Rice



CASING:
 16" 140'
 85/8" 3235'

Elevation. 1803

Production. Pot. 2098 B.

Figures Indicate Bottom of Formations.

red bed & sand	145
shale	225
sand	275
lime shells & shale	335
red bed	420
shale blue & red	563
shale blue & lime shells	670
shale grey & lime shells	770
shale blue & lime shells	1020
salt	1150
salt & lime shells	1270
shale blue & lime shells w/ salt strks	1297
anhydrite & blue shale brks	1360
lime hrd & shale	1425
lime & shale	1430
lime	1460
shale & lime shells	1469
lime	1486
lime grey & shale	1556
lime grey hrd	1567
shale blue strks & lime	1583
lime hrd	1600
shale	1625
lime	1645
shale & lime shells	1674
lime	1687
shale & shells	1707
lime	1718
shale blue & shells	1742
lime	1749
lime & blue shale strks	1799
lime hrd	1839
lime	1890
shale sticky white	1908
shale grey	1916
lime grey w/blue shale strks	1975
shale & lime	2163
shale blue & lime shells	2212
lime & shale	2274
lime	2281
shale sticky blue	2288
shale blue & lime shells	2368
shale & lime	2512
shale blue & lime	2536
shale & lime	2650
lime	2786
lime w/sm blue shale brks	2823
lime	2868
shale blue & shells	2933
shale & lime	2960
lime	2991
lime & shale	3045
lime	3079
lime & blue shale	3090
lime	3157
lime & shale brks	3188
lime	3244 $\frac{1}{2}$
Total Depth.	

3235
 1803
 -1432

Arbuckle lime 3235-3244 $\frac{1}{2}$