


GULF OIL CORP.
W.R. Ames No. 5.

SEC. 6 T.18 R. 10W
CN $\frac{1}{2}$ SE NW

Total Depth. 3236'
Comm. 5-10-40 Comp. 5-28-40
Shot or Treated. 5-28-40 2000 Gals. Acid
Contractor.
Issued. 8-3-40

County. Rice



CASING:
8 5/8" 204'
5 1/2" 3229'

Elevation.

Production. Pot. 3000 B.
Figures Indicate Bottom of Formations. No wtr, Sonic Meter

surface clay & shells	208
red bed, shale & shells	500
shale & shells	705
anhydrite	740
shale & shells	1025
salt & shells	1148
shale & shells	1322
anhydrite	1380
lime brkn & shale	1425
shale & shells	1515
lime brkn	1550
lime	1588
shale & shells	1655
lime	1878
lime brkn & shale	1944
shale & shells	2270
lime brkn	2295
shale & shells	2525
lime brkn	2560
shale & lime	2616
lime	2645
lime brkn	2710
lime	2785
lime Topeka	2831
lime Topeka & shale	2934
shale	2950
lime KC	3088
lime	3155
lime KC	3191
lime & conglomerate	3223
lime & oil sand	3236
Total Depth.	

Top Kansas City Lime 2955
Arbuckle lime 3229-3236