


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

TRANSWESTERN OIL CO.
Pauline Roesler No. 4

SEC. 6 T. 18 R. 10W.
CNL NE SW

Total Depth. 3264
Comm. 8-7-40 Comp. 8-28-40
Shot or Treated.
Contractor.
Issued. 10-19-40

County Rice.



CASING.

103/4" 200'
5 1/2" 3240'

Elevation.

Production. Pot. 4092 B.

Figures Indicate Bottom of Formations.

shale and shells	226
shale and shells	740
shale shells & salt	1255
shale and shells	1438
lime and shale	1722
lime small shale	
breaks	1835
lime and shale	1940
broken lime	2055
shale and lime	2332
lime and shale	2870
lime and shale	2967
lime	3240
Drilling cement	3244
No log	3250
brown soft chunks	3252
dolomite mod soft	
little sat.	3253
hard dolomite no sat.	3254
Dolomite	3264
Total Depth.	

dolomite nice show and well sat. 3240-44
hole filled 400' in one hour.
dolomite, little sat. filled 950'
in two hours.
dolomite soft nice sat. more oil-
hole filled 2600' in 4 hours. 3246-3249

Top of Arbuckle 3239