

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

TRANSWESTERN OIL CO.  
Habiger No. 17C.


SEC. 8 T. 18 R. 10W.  
SWc NE

Total Depth. 3268  
Comm. 8-19-38 Comp. 9-28-38  
Shot or Treated.  
Contractor. Iron Drlg. Co.  
Issued. 10-22-38

County. Rice.

CASING.

103/4" 240'8  
7" 3265'



Elevation.

Production. Pot. 185 bbls.,

Figures Indicate Bottom of Formations.

surface clay & sand	35
sand sholls & shalo	90
shalo and sholls	200
sand	225
shalo	253
rod bed	490
anhydrite limo	525
rod bed and shalo	610
rod rock	790
shalo and sholls	885
shalo and sholls	962
salt	1191
shalo and limo	1415
shalo	1420
limo	1540
limo and shalo	1642
shalo and limo	1717
shalo and limo	1772
limo	1787
limo and shalo	1817
limo and shalo	1900
shalo and limo	1958
rod bed and shalo	1977
limo and shalo	2126
shalo and sholls	2218
shalo	2238
shalo and sholls	2243
shalo	2349
brokon limo	2382
shalo and sholls	2446
shalo	2536
brokon limo and shalo	2578
limo	2605
limo and shalo	2630
limo	2680
limo and streaks of shalo	2724
limo and shalo	2810
limo	2822
sdv shalo and limo	2880
limo	2928
limo	3008
corod limo	3042
limo	3091
limo with shalo strks	3143
limo and shalo	3265
siliceous limo	3268

Total Depth.

The Kansas City limo was tested by perforating after casing was set at Top of Siliceous limo. As. K.C. was not commercially productive the perforations were squeezed off and well completed in Sil limo Hole filled 750' in 8 hours Oil and water.