


EARL F. WAKEFIELD ET AL
Schultz No. 1.

SEC. 22 T. 18 R. 10 W
CW $\frac{1}{2}$ NE NW

Total Depth. 3263'
Comm. 6-4-42 Comp. 7-16-42
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 8-22-42

County. Rice



CASING:

12 $\frac{1}{2}$ " 452'
10" 1825' UR 1905'
8 $\frac{1}{4}$ " 2541'
65/8" 3164'
5 $\frac{1}{2}$ " 3249'

Elevation.

Production. Pot. 999 B.

Figures Indicate Bottom of Formations.

cellar	10	shale & shells	1990	Geological Data: Top Lansing 2920) sample top Top Arbuckle 3245) corrected Correction was 3257 - 3248
clay yellow	55	shale blue	2003	
shale red	65	lime	2015	
shale blue	80	shale blue	2045	
shale lgt	90	lime	2055	
shale blue	130	shale	2080	
sand wtr	158	lime	2085	
lime	162	shale & shells	2105	
shale blue	180	shale	2118	
sand shale (HFW 180-200)	200	shale & shells	2140	
shale blue	247	shale	2215	
shale red	448	lime	2228	
anhydrite	465	shale	2235	
shale blue	470	lime	2240	
shale red	710	shale	2275	
shale blue	910	lime	2295	
salt	1170	shale	2300	
lime	1175	lime	2305	
shale	1185	shale & shells	2385	
lime	1190	shale	2425	
shale blue	1200	lime	2450	
lime	1210	shale blue	2460	
shale blue	1217	lime	2480	
red rock	1222	shale	2485	
shale blue	1235	lime	2490	
shale & lime shells	1305	shale dk	2515	
shale blue	1320	lime	2532	
shale brown	1325	shale	2537	
shale & shells	1350	lime	2573	
lime	1365	shale	2577	
shale blue	1380	lime	2630	
lime	1410	shale	2638	
shale blue	1425	lime	2690	
shale red	1440	shale blk	2695	
1BW 1440-50 2BW 1525-35		lime 1BW 2735	2782	
lime 4BW 1560-75	1600	shale	2785	
shale brown	1605	lime	2790	
lime	1665	shale	2800	
shale dk	1675	lime (1BW 2815-20)	2810	
lime	1680	shale	2815	
shale blue	1690	lime	2820	
red rock	1695	shale	2898	
lime	1703	lime	2905	
shale blue	1708	shale	2922	
lime	1714	lime	2945	
red rock	1718	shale	2950	
lime	1737	lime sh gas 2952	2990	
shale blue	1743	shale	2994	
shale red	1750	lime & shale	3073	
lime	1770	lime sh oil 3092	3189	
shale	1780	conglomerate & shale	3245	
lime	1810	lime	3263	
shale red	1827	Total Depth.		
lime 4BW 1870-80	1890			
shale blue	1900	sh oil 3245-52		
red rock	1908	1100' oil in 1 hr 3258-		
lime	1940	63		
shale	1950			
lime	1978			