


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

TRANSWESTERN OIL COMPANY.
Henry Roelfs (Culbertson) No. 1.

SEC. 26 T. 18 R. 10W.
CSL NE NE

Total Depth. 3218
Comm. 1-10-41 Comp. 2-1-41
Shot or Treated.
Contractor. Iron Drilling Co.
Issued. 4-5-41

County Rice.



CASING.

85/8" 290' cemented.
5 1/2" 3178' cemented.

Elevation. 1745

Production. Pot. 938 B.

Figures Indicate Bottom of Formations.

surface hole	130
shale and shells	295
red shale and shells	525
shale shells and salt	955
salt strks shale and shells	1195
lime and shale	1610
lime	1717
lime and shale	1960
shale and shells	2075
shale and lime	2185
shale	2200
lime	2324
lime and shale	2510
lime	2619
broken lime	2680
lime	2748
lime and shale breaks	2828
shale	2880
K.C. lime	2963
lime	3121
lime and shale	3173
lime	3178
Rotaty total depth.	
Drilling cement.	
No formation shown	3182
conglomerate, cherty with red shale	3190
red sdy shale, pieces chert	3201
red shale, pieces chert	3204
sdv chert, pieces red shale	3209
chert pieces green sdy shale	
lots sand grains	3211
quartz white little cherty	3212
quartz, brown soft	3216 More Oil
quartz, hard whiter	3218
Total Depth.	

3216 Hole filled to within 100' top hole