


SLICK PRYOR AND LOCKHART
 Habiger No. 1

SEC. 27 T. 18 R. 10W
 NE NW SE

County. Rice.

Total Depth. 3242 1/2
 Comm. 12-29-33 Comp. 2-6-34
 Shot or Treated.
 Contractor. Murray Drilling Co.
 Issued. 2-24-34

Scanned at Wichita
 Attached Well Header
 VIA FTP



Set Tops
 Cong 3170

CASING

20" 100' 10" 1783'8"
 15 1/2" 180' 8" 2480'
 13" 437' 6 5/8" 2902'
 5 3/16" 3154'

Elevation. 1747

Production. 336 bbls., Pot.

Figures Indicate Bottom of Formations.

Cellar	12	lime	1565
mud light	30	show gas	1530
mud yellow	67	lime	1575
clay yellow	100	shale blue	1585
mud yellow	110	sdv shale	1615
slate blue HFV 120-30	120	lime	1630
water sand	155	slate B.	1635
slate blue	165	lime	1645
slate blue	180	red rock	1650
shale blue	200	lime	1675
water sand	205	red rock	1685
2 BWPHR 200-205		lime	1690
shale blue	225	lime	1695
shale blue	245	slate blue	1715
shale white & BWPHR 250-260	250	lime	1720
red rock	300	shale blue	1725
shale red	405	lime	1730
hole is making 9 BWPHR		slate blue	1735
shale red	435	shale blue	1740
Anhydrite lime	437	lime grey	1755
lime	450	shale blue	1765
red rock	477	lime grey	1780
red rock	700	red rock	1785
shale blue	760	Corr. Meas of 8 ft O.K. at 1785	
shale red	780	red rock	1792
shale blue	785	lime	1796
red rock	810	lime	1825
slate white	825	slate blue	1830
slate blue	870	shale blue	1855
shale blue	925	lime white	1860
salt	940	slate blue	1875
salt	1125	shale red	1885
salt and light shale	1165	lime grey	1930
salt	1170	showing of gas	1890
slate blue	1225	lime	1935
slate blue	1230	slate blue	1955
lime grey	1245	hole caving.	
slate blue	1255	slate blue	1975
lime grey	1265	hole caving.	
slate blue	1275	lime grey	1980
shale light	1280	slate blue	2000
red rock	1295	shale blue	2015
shale light 1/2 BW 1310	1308	lime	2020
lime broken	1330	lime Hole caving	2030
shale light	1335	slate blue	2040
slate dark	1350	good show gas	2040-45
	1360	broken lime	2050

Slick Pryor and Lockhart.
 Habiger No. 1. 27-18-10W Rice County

shale blue	2230
lime	2250
slate blue	2255
lime	2260
slate blue	2270
lime grey	2295
red rock	2300
shale light	2310
shale blue	2312
lime caving.	2340
lime	2360
3 BWPHR 2340-50	
slate blue	2375
lime	2995
shale blue	2410
shale blue	2460
broken lime	2475
2 BWPHR 2470-2475	
lime white	2478
lime	2485
slate blue	2490
lime	2520
1/2 BWPHR 2600	
show oil 2682-2696	Reduced hole 2696
lime grey	2755
lime and shale breaks	2765
shelly lime and slate	2790
shale blue	2795
lime broken	2825
shale blue	2850
lime	2865
hole caving.	
shale and lime shells	2877
lime	2885
showing of gas 2884	
lime	2903
Hole caving bad	
1st show gas. 2926	
lime	2958
sand	2960
Got 2,000,000 ft gas 2958 to 2960 and	
water is spraying 25 ft high water	
coming below gas.	
sand grey	2985
lime	2998
lime	3055
lime white	3059
shale blue	3063
lime white	3090
1/2 BW 3090	
showing of oil in lime 3150-3154	

lime white	3174
conglomerate	3210
conglomerate	3234
quartzite	3236
Top of Quartzite	3234
quartzite soft	3238
1st show oil 3234-36	
hole filled 800' from	3236-38
in 50 Min.	
quartzite soft	3242 1/2 T.D.

65/8 " Casing UR 2912 UR2924'5"
 UR 2955'2" UR 2990 UR 2996'9

2850
 1749
 1103

4861
 1741
 7225