

October, 1934.

Slick, Pryor, and Lockhart #2 Herzog.
NW NE SE. 27-18S-10W.
Elevation 1746'

Pennsylvanian conglomerate 3186-3211'

3186-3192 Clay, red and green, platy, with silty streaks. May be residual.

3192-3211 Chert, clays, and rare sand. May be residual but appears more like thin layers of cherty conglomerate in shale.

Sub-sea minus 1465'

Pre-Cambrian Top 3211'
3211-3219 Quartzite.

No dolomite is present in this well. As noted above, the cherts on top of the Pre-Cambrian more nearly suggest a conglomerate than a deposit of residuum from weathered dolomite.