

27-18-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. HONAKER DRILLING CO., INC.
Farm. Robl No. 1

SEC. 27 T. 18 R. 11W
SE SE SE

Total Depth. 3370
Comm. 9-10-51 Comp. 9-21-51
Shot or Treated.
Contractor. Honaker Drllg Co., Inc.
Issued. 10-27-51

County Barton
KANSAS



CASING:

8 5/8" 192' cem w/125 sx.

Elevation. 1772 BB

1777(m)

Production. Dry

Figures Indicate Bottom of Formations.

clay, shale	201	Streaks poor porosity,
shale, red bed	605	light spotted saturation.
shale, shells	1115	Faint sulphur odor 3360-70
salt	1185	
shale, shells	1495	
lime	1640	
lime, shale	1700	
lime	2005	
shale, lime	2695	
lime	2780	
lime, shale	2860	
lime	2905	
shale, lime	3060	
lime	3105	
lime, shale	3170	
lime	3370 RTD	
Total Depth		

Tops:
Heebner 2896
Brown Lime 3012
Kansas City 3027
Conglomerate 3323
Arbuckle 3344

Johnston Drill Stem Test:
Packer set at 3073. T.D.
3105. Tool open 50 mins.
Weak blow for 45 mins. Rec.
20' mud, No BHP.

Packer set at 3347-58.
Tool open 30 mins. weak
blow for 3 minutes. Rec.
6' mud. No BHP.

Shows:

Trace poor porosity,
light spotted stain. No
free oil. No odor 3036-39

Trace poor porosity,
light spotted stain,
faint odor. No free
oil 3074-78

Trace poor porosity,
light spotted stain,
no odor. No free oil 3097-3100

No saturation,
No odor 3114-3175

No porosity, no sat. 3344-54

Faint odor. Show free
oil. 3354-58

No poro. no sat. 3358-60