

DRILLERS WELL LOG

BROUGHER OIL, INC.
P.O. Drawer 1367
Great Bend, Ks 67530

SCHEPMAN #4: API#15-009-23,630
SE NW SW Sec. 16-18-11W
Barton County, Kansas 67530

SURFACE PIPE: 8 5/8" Surface Casing set at 334',
cemented with 180 sacks of 60/40 Pozmix, 2% Gel,
3% C.C., cement did circulate.

PRODUCTION CASING: 5 1/2" Production casing set at 3362',
cemented with 50/50 Pozmix, 18% Salt, .75% CFR-2,
20 barrels salt flush, 5# Gilsonite per sack, 150 sacks.

DATE COMMENCED: 7-18-84
DATE COMPLETED: 7-24-84

0 -	334'	Sand & Shale
334 -	641'	Shale & Red Bed
641 -	662'	Anhydrite
662 -	1106'	Shale
1106 -	1465'	Shale
1465 -	1490'	Shale
1490 -	1994'	Shale
1994 -	2315'	Shale & Lime
2315 -	2658'	Shale & Lime
2658 -	2917'	Shale & Lime
2917 -	3097'	Shale & Lime
3097 -	3128'	Shale & Lime
3128 -	3162'	Lansing Lime
3162 -	3256'	Lime & Shale
3256 -	3360'	Lansing Lime
3360 -	3375'	Arbuckle
3375 -	3377'	Arbuckle
	3377'	RTD

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Terry Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Terry L. Williamson
Terry Williamson

Subscribed and Sworn to before me this 1st day of August, 1984.

My Commission Expires: 6-9-86

Jeri Pehley
Notary Public

