

MAY 31 1969

11-18-12W

DRILLERS' WELL LOG

DATE COMMENCED: March 9, 1969
DATE COMPLETED: March 19, 1969

Pyramid Corporation, Inc.
KINZEL #1
NE/4 NE/4 NE/4
Section 11-18-12W
Barton County, Kansas

ELEVATION: 1869 K.B.

prod: Dry

FORMATION TOPS

0	-	40'	Clay & Post Rock
40	-	540'	Shale & Sand Streaks
540	-	730'	Red
730	-	760'	Anhydrite
760	-	1675'	Shale & Shells
1675	-	2165'	Lime & Shale
2165	-	2688'	Shale & Lime
2688	-	3018'	Lime
3018	-	3022'	Shale
3022	-	3036'	Lime & Shale
3036	-	3057'	Lime
3057	-	3124'	Shale
3124	-	3136'	Brown Lime
3136	-	3382'	Lime
3382	-	3412'	Conglomerate
3412	-	3507'	Dolomite
3507			RTD

ANHYDRITE	730
HOWARD LIME	2688
TOPEKA	2764
HEEBNER	3018
TORONTO	3036
DOUGLAS	3057
BROWN LIME	3124
KANSAS CITY	3136
BASE K.C.	3382
ARBUCKLE	3412
RTD	3507

SURFACE CASING: Set used 28#
8-5/8" at 235' with 170 sacks
cement.

PRODUCTION CASING: Set used
5 1/2" 14#, at 3506' with 125
sacks cement (salt sat. pozmix)

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age, does hereby swear and state that
the facts and statements herein contained are true and correct to
the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this _____ 1969.

