


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company- COOPERATIVE REFINERY ASS'N.
 Farm- Zink "A" No. 2

SEC. 35 T. 18 R. 12W
 C E/2 NE SE

Total Depth. 3465'
 Comm. 5-2-59 Comp. 5-13-59
 Shot or Treated.
 Contractor. Shields Drlg.
 Issued. 3-1-59

County Barton
 KANSAS



Elevation. 1809' KB

CASING:
 8 5/8" 674' cem w/350 sx.
 4 1/2" 3438' cem w/125 sx.

Production. 40 BOPD

Figures Indicate Bottom of Formations.

shale, shells, sand	410
shale	664
Anhydrite	685
shale	710
shale & shells	1460
shale & lime	1895
broken lime	1990
shale & lime	3100
lime	3370
lime & Conglomerate	3420
lime	3465 RTD
Total Depth	

TOPS: SCOUT	
Heebner	2986
Toronto	3009
Douglas	3024
Brown Lime	3102
Lansing	3118
Base Kansas City	3382
Arbuckle	3419